



NOTES:

1. THE TRENCH BOTTOM SHALL BE FREE FROM LARGE STONES, DIRT CLOUDS, AND ANY FROZEN MATERIAL PRIOR TO PLACING PIPE.
2. BELL HOLES SHALL BE PROVIDED TO INSURE A UNIFORMLY SUPPORTED PIPE.
3. PIPE AND ACCESSORIES SHALL BE LOWERED INTO THE TRENCH IN SUCH A MANNER AS TO PREVENT DAMAGE TO THEM. ANY DAMAGED OR DEFECTIVE MATERIAL SHALL BE REPLACED OR REPAIRED, AND ALL FOREIGN MATERIAL OR DIRT SHALL BE REMOVED FROM THE INTERIOR OF THE PIPE.
4. THE INITIAL BACKFILL SHALL BE FREE FROM ROCK LARGER THAN 3/4", LARGE DIRT CLOUDS, AND FROZEN MATERIAL.
5. INITIAL BACKFILL SHALL BE COMPLETED IN 6" LAYERS TO 6" ABOVE THE PIPE AND COMPACTED BY HAND TAMPING. THE REMAINING BACKFILL CAN BE PLACED BY MACHINE IN EVEN LAYERS WITH NO STONES LARGER THAN 4" IN DIAMETER.
6. ROLLING EQUIPMENT CAN BE USED WHEN 18" OF FILL HAS BEEN PLACED ABOVE THE PIPE.
7. INSTALLATION PRECAUTIONS SHALL BE IN COMPLIANCE WITH A.S.T.M. SPEC D-2321.
8. IN ROCK, PROVIDE MINIMUM 6" TYPE I BEDDING UNDER PIPE.